



ESTIMATE

11/24/2021

Estimate **9873**

Proposal Made To

PEAK BUILDING CORPORATION
1706 VINTON CIRCLE
CHESAPEAKE, VA 23323

Ship To

1285 HEBDEN COVE
VIRGINIA BEACH, VA 23452

EAP Rep	EAP Job #	Project
JB		BOHANNON ADDITION

DESCRIPTION	QUANTITY	TOTAL
CUSTOM ENTRY DOOR		
DR1 - ENTRY DOOR	1.00	9,178.76T
2 32" X 84" X 1 3/4" Mahogany 6 panel Doors with our standard raised molding 1 84" X 1 3/4" Mahogany Kerfed T-Astragal; Includes weatherstripping and boot 2 12" X 84" X 1 3/4" Mahogany Full Lite side Lites to accommodate 5/8" glazing 2 Clear Tempered Insulated Glass for Side Lites 1 Clear Tempered Insulated Glass for Transom Sashes 1 Mahogany Jamb for Double Doors & 2 Side Lites Based on 4 9/16" Wall Thickness; Jamb Includes: 2" brick mold, adjustable anodized (dark bronze) aluminum threshold, compression weather-stripping & sweeps 2 Pre-hang; Cut for 3 Hinges per Door 6 Emtek 4" Hinges for Doors (ORB) 1 Cut for and Provide Flushbolts 1 Cut for a standard double bore in Active Door Only 1 Crating Charge		
OPTION TO STAIN AND FINISH - CHOICE FROM MANUFACTURERS'S STANDARD COLORS		

ADD \$2119.60

We look forward to working with you on this and future projects !

Terms 50% DOWN/BALANCE ON DELIVERY

MAKE CHECKS PAYABLE TO: ERVIN ARCHITECTURAL PRODUCTS.

A 3% CONVENIENCE FEE WILL BE ADDED FOR ALL CREDIT CARD PAYMENTS

A finance charge of 1.5 % per month will be charged on all accounts past due.
Ervin Architectural Products shall be entitled to recovery all costs of collection including reasonable attorney fees. Quote valid for 30 days.

Subtotal	\$9,178.76
Sales Tax (6.0%)	\$550.73

TOTAL \$9,729.49

Approved by _____