
JM FROEHLER - GLEYSTEEN RESIDENCE TURRET WINDOWS- SIGNATURE ULTIMATE

Quote #: H3KALGD

A Proposal for Window and Door Products prepared for:

Job Site:

23310



ERVIN ARCHITECTURAL PRODUCTS 1255 CAROLINA RD SUFFOLK, VA 23434-8729



ERVIN ARCHITECTURAL PRODUCTS
PO BOX 2715
VIRGINIA BEACH, VA 23450-2715
Phone: (757) 427-2929

This report was generated on 1/18/2022 4:08:11 PM using the Marvin Order Management System, version 0003.12.00 (Current). Price in USD. Unit availability and price are subject to change. Dealer terms and conditions may apply.

Project Description:

WINDOW <T> HINGE SIDES VERIFIED- RH, VIEWED FROM EXTERIOR; EXTERIOR COLOR STONE WHITE; FRAME WIDTH 23.5" TO MATCH WINDOW WIDTH BELOW

Featuring products from:



JM FROEHLER - GLEYSTEEN RESIDENCE TURRET WINDOWS- SIGNATURE ULTIMATE

Quote Number: H3KALGD

UNIT SUMMARY

The following is a schedule of the windows and doors for this project. For additional unit details, please see Line Item Quotes.

Additional charges, tax or Terms and Conditions may apply. Detail pricing is per unit.

NUMBER OF LINES: 1	TOTAL UNIT QTY: 5	EXT NET PRICE: USD 19,633.85
--------------------	-------------------	------------------------------

LINE	MARK UNIT	PRODUCT LINE	ITEM	QTY
1	Т	Ultimate	Casement Operator Round Top	5
			RO 24 1/2" X 62"	


OMS Ver. 0003.12.00 (Current) Processed on: 1/18/2022 4:08:11 PM Page 2 of 4

Quote Number: H3KALGD

LINE ITEM QUOTES

The following is a schedule of the windows and doors for this project. For additional unit details, please see Line Item Quotes. Additional charges, tax or Terms and Conditions may apply. Detail pricing is per unit.

Line #1	Mark Unit: T	Net Price:		3,926.77
Qty: 5		Ext. Net Price:	USD	19,633.85



As Viewed From The Exterior

RO 24 1/2" X 62"
Egress Information
Width: 17 61/64" Height: 4.

Width: 17 61/64" Height: 44 41/64" Net Clear Opening: 5.56 SqFt Stone White Clad Exterior
Painted Interior Finish - White - Pine Interior
Ultimate Casement Operator Round Top - RT2
Right Hand
Rough Opening Springline from bottom: 49 3/4"
Frame Size 23 1/2" X 61 1/2"
FS Springline from bottom: 49 3/4"
IG - 3/4" - 1 Lite

Low E2 w/Argon
Stainless Perimeter Bar
Ogee Interior Glazing Profile
Standard Bottom Rail

White Weather Strip White Folding Handle White Multi - Point Lock Stainless Steel Hardware

Brushed Stainless Steel Butt Hinge

Aluminum Screen
White Surround
Bright View Mesh
***Screen/Combo Ship Loose
6 9/16" Jambs

Nailing Fin

***Note: Rotating wash mode hardware is not available on Ultimate Round Top operating units.

***Note: Unit Availability and Price is Subject to Change

Project Subtotal Net Price: USD 19,633.85 6.000% Sales Tax: USD 1,178.03 Project Total Net Price: USD 20,811.88

TERMS AND CONDITIONS

- All Marvin Pricing Valid for 30 days.
- All custom Requires 50% Deposit at time of order placement / Shop drawing approval.
- All Pricing is for material only unless otherwise stated.
- •While we have done our best to quote this project accurately, it is your responsibility to determine that we have quoted what you and your customer want including suitability, Local Code Compliance, and fitness for purpose.
- Review this order carefully. Marvin product is made to order and is not returnable. We cannot accept changes/cancellations after your order has been signed off on and released into production.
- We cannot release and order unless this sheet is signed, dated, and returned to Ervin Architectural Products along with deposit.

JM FROEHLER - GLEYSTEEN RESIDENCE TURRET WINDOWS- SIGNATURE ULTIMATE

Quote Number: **H3KALGD**

PURCHASE APPROVAL/SIGN OFF

Project Subtotal Net Price: USD	19,633.85
6.000% Sales Tax: USD	1,178.03
Project Total Net Price: USD	20,811.88
I have reviewed all line item quotes in detail and agree that the product specifications and pricing are accuapprove the project for order. I acknowledge that additional charges, tax or Terms and Conditions may ap	•
Buyer: • Installation Option - \$ 1,125.00	
• INSTALLATION OF WINDOW UNITS AS LISTED IN QUOTE ABOVE; ALL UNITS SHALL BE INSTALLED AS PE MANUFACTURERS WRITTEN INSTRUCTIONS AND BY FACTORY TRAINED / INSTALLATION MASTERS CERT INSTALLERS, METHOD "A1" INSTALLATION. ALL FLASHING MATERIALS INCLUDED COMPLY WITH ASTM SECTION 5.13. (6" BUTYL FLASHING TAPE & FLEX TAPE SILLS, CAULK, LOW EXPANSION FOAM, SHIMS & F	IFIED E2112-01,
• ANY ALTERATION TO OPENINGS NEEDED TO ALLOW FOR PROPER INSTALLATION OF WINDOW/DOOR WILL BE HANDLED ON A TIME AND MATERIALS BASIS WITH PRIOR APPROVAL FROM GC.	PRODUCTS
• INSTALLERS SHALL CLEAN UP AND DISPOSE OF INSTALLATON RELATED DEBRIS (GC PROVIDED DUMPS)	ΓER).
Buyer:	

OMS Ver. 0003.12.00 (Current) Processed on: 1/18/2022 4:08:11 PM Page 4 of 4