



ESTIMATE

1/20/2022

Estimate 9976

Proposal Made To

JM FROEHLER CONSTRUCTION
2251 W. GREAT NECK RD
VIRGINIA BEACH, VA 23451

Ship To

LOT 7, BUTLER'S BLUFF
CAPE CHARLES, VA 23310

EAP Rep	EAP Job #	Project
JB		GLEYSTEN RESIDENCE

DESCRIPTION	QUANTITY	TOTAL
FRONT DOOR (Revised 1/20/22)		
CUSTOM ENTRY DOOR - SIMILAR TO DBYD-1042 WITH A RECTANGULAR TRANSOM		15,898.89T
2 - 36" X 96" X 1 3/4" Mahogany "H" Doors with our standard raised molding; To accommodate 1" glazing		
2 - Leaded Textured glass for Door		
2 - Insulate leaded glass in Door with Clear Tempered glass on both sides		
1 - 96" X 1 3/4" Mahogany Kerfed T-Astragal; Includes weather-stripping and boot		
1 - 12" Mahogany full lite Transom sash; To accommodate 1" glazing		
1 - Leaded Beveled & Textured glass for Transom		
1 - Insulate leaded glass in Transom with Clear Tempered glass on both sides		
1 - Mahogany Jamb for Double Doors & a Rectangular Transom; Based on 6 9/16" Wall Thickness; Jamb Includes: Adjustable anodized (dark bronze) aluminum threshold, compression weather-stripping & sweep		
2 - Pre-hang; Cut for 4 Hinges per Door (RH / IN - Active)		
8 - Emtek 4" Hinges for Door -		
*****PLEASE PROVIDE HINGE FINISH COLOR _____		
1 - Cut for and provide Baldwin Flush Bolts		
1 - Cut for Cylinder Hardware		
1 - Stain and Finish Unit		
1 - Crating Charge		
1 - Freight		

We look forward to working with you on this and future projects !

Terms 50% DEPOSIT / BAL ON COMPLETION

MAKE CHECKS PAYABLE TO: ERVIN ARCHITECTURAL PRODUCTS.

Subtotal
Sales Tax (6.0%)

TOTAL

A 3% CONVENIENCE FEE WILL BE ADDED FOR ALL CREDIT CARD PAYMENTS

Approved by



ESTIMATE

1/20/2022

Estimate 9976

Proposal Made To

JM FROEHLER CONSTRUCTION
2251 W. GREAT NECK RD
VIRGINIA BEACH, VA 23451

Ship To

LOT 7, BUTLER'S BLUFF
CAPE CHARLES, VA 23310

EAP Rep	EAP Job #	Project
JB		GLEYSTEN RESIDENCE

DESCRIPTION	QUANTITY	TOTAL
-------------	----------	-------

OPTIONS:
2" Brick Mould and 3-1/4" Standard Mahogany Interior Casing - ADD \$361.50

***** INIT _____

THE BALDWIN MONTEREY HANDLESET SHOWN WITH DBYD-1042 WAS DISCONTINUED.

PLEASE PROVIDE NEW HANDLESET CHOICE. _____

INSTALLATION OF ENTRY DOORS	1.00	1,250.00
-----------------------------	------	----------

EAP TO PROVIDE:
LABOR
FOAM
FLASHING TAPE
FASTENERS
CUSTOM FABRICATED SILL PANS WITH MARVIN HD ALUMINUM COIL
STOCK WITH AAMA 2605 PAINT FINISH

We look forward to working with you on this and future projects !

Terms 50% DEPOSIT / BAL ON COMPLETION

MAKE CHECKS PAYABLE TO: ERVIN ARCHITECTURAL PRODUCTS.

A 3% CONVENIENCE FEE WILL BE ADDED FOR ALL CREDIT CARD PAYMENTS

A finance charge of 1.5 % per month will be charged on all accounts past due.
Ervin Architectural Products shall be entitled to recovery all costs of collection including reasonable attorney fees. Quote valid for 30 days.

Subtotal	\$17,148.89
Sales Tax (6.0%)	\$953.93

TOTAL \$18,102.82

Approved by _____