



ESTIMATE

3/30/2022

Estimate 10115

Proposal Made To

R.L. BLOUNT CUSTOM HOMES
P.O. BOX 9902
CHESAPEAKE, VA 23321

Ship To

GOVERNOR'S POINT - LOT 37
240 WENTWORTH COURT
SUFFOLK, VA 23436

EAP Rep

EAP Job #

Project

JB

KATHLEEN & MICHAEL RESIDENCE

DESCRIPTION	QUANTITY	TOTAL
ENTRY DOOR(REVISED 3/30/22)		
EXTERIOR DOORS	1.00	16,176.00T
2 42" X 108" X 2 1/4" Mahogany custom 7 lite over 1 panel Doors with no raised molding; To accommodate 5/8" glazing		
2 Clear Tempered Insulated glass for Doors		
1 108" X 2 1/4" Mahogany Kerfed T-Astragal; Includes weather-stripping and boot		
1 36" X 2 1/4" Mahogany 2 lite Rectangular Transom sash; To accommodate 5/8" glazing		
1 Clear Tempered Insulated glass for Transom		
1 Mahogany Jamb for Double Doors; Based on 4 9/16" Wall Thickness; Jamb Includes: 2" brick mold, adjustable anodized (dark bronze) aluminum threshold, compression weather-stripping & sweeps		
1 Mahogany Jamb for a Rectangular Transom; Based on 4 9/16" Wall Thickness; Jamb Includes: 2" brick mold		
1 Our standard 3 1/4" Mahogany interior casing		
2 Pre-hang; Cut for 4 (4 1/2") Hinges per Door		
8 Emtek 4 1/2" Ball Bearing Hinges for Doors		
1 Cut for and provide Baldwin Flush Bolts		
1 Cut for Cylinder Hardware in Active & Dummy Doors		
SHIPPING FROM DOOR MANUFACTURER	1.00	825.00
OPTION TO MACHINE FOR MORTISE HARDWARE - ADD \$240.00 + TAX		
INIT _____		

We look forward to working with you on this and future projects !

Terms 50% DOWN/BALANCE ON DELIVERY

MAKE CHECKS PAYABLE TO: ERVIN ARCHITECTURAL PRODUCTS.

Subtotal

Sales Tax (6.0%)

TOTAL

A 3% CONVENIENCE FEE WILL BE ADDED FOR ALL CREDIT CARD PAYMENTS

Approved by



ESTIMATE

3/30/2022

Estimate 10115

Proposal Made To

R.L. BLOUNT CUSTOM HOMES
P.O. BOX 9902
CHESAPEAKE, VA 23321

Ship To

GOVERNOR'S POINT - LOT 37
240 WENTWORTH COURT
SUFFOLK, VA 23436

EAP Rep

EAP Job #

Project

JB

KATHLEEN & MICHAEL RESIDENCE

DESCRIPTION	QUANTITY	TOTAL
OPTION FOR 6-9/16" JAMBS - ADD \$345.00 + TAX		
INIT _____		
OPTION TO STAIN AND FINISH UNIT - ADD \$1,484.00 + TAX		
INIT _____		
INSTALLATION OF ENTRY DOORS	1.00	1,650.00
EAP TO PROVIDE: LABOR FOAM FLASHING TAPE FASTENERS CUSTOM FABRICATED SILL PANS WITH MARVIN HD ALUMINUM COIL STOCK WITH AAMA 2605 PAINT FINISH		

We look forward to working with you on this and future projects !

Terms 50% DOWN/BALANCE ON DELIVERY

MAKE CHECKS PAYABLE TO: ERVIN ARCHITECTURAL PRODUCTS.

A 3% CONVENIENCE FEE WILL BE ADDED FOR ALL CREDIT CARD PAYMENTS

A finance charge of 1.5 % per month will be charged on all accounts past due.
Ervin Architectural Products shall be entitled to recovery all costs of collection including reasonable attorney fees. Quote valid for 30 days.

Subtotal \$18,651.00
Sales Tax (6.0%) \$970.56

TOTAL \$19,621.56

Approved by _____